

## **CONSTRUCTOR**

V1.2 HIGH FLOW EDITION

Uniquely designed for carrying and operating large tools and modules

















## **CONSTRUCTOR V1.2 HIGH FLOW EDITION**

The CONSTRUCTOR technology is refined from years of operational and "hands-on" experience by our designers. The top-side control system for KYSTDESIGN ROV's is designed with focus on providing an ergonomic, intuitive and efficient working environment. Single or dual operation stations can easily be configured to individual needs. Operator task priorities can be switched and shared between stations during operation. The CONSTRUCTOR can accommodate up to 25 additional hydraulic tooling functions, up to 21 additional survey sensors and 9 camera connectors. All hydraulic functions are proportionally controlled, and all electrical power supplies are ground fault monitored. The ROV control system offers a variety of auto-functions like AutoPOS and AutoTRACK capabilities. Remote control is also available.

GENERAL	
Power	160 Kw / 220 Hp
DDepth rating ROV	3000 (up to 6000 optional) msw
Depth rating Buoyancy	3000 (2000, 4000, 6000 optional) msw
Dimensions (LxBxH)	3,22 m X 1,7 m X 1,87 m
Weight	4600 kg
Payload	450 kg
Through Frame Lift capacity	3000 kg
Thrusters	7x SA380
MECHANICAL C	CAPACITY AND INTERFACES
Free space inside ROV for utility equipment:	Open area on approx. 460 L through the entire ROV, right in front of centre of gravity.
Interface for work modules:	Four docking receptacles underneath the ROV. Interface for Sensors frame and/or modules by threaded inserts on all sides of the buoyancy element.
Manipulators:	Interface for Schilling T4, RigMaster and Atlas
HYDRAULIC CA	PACITY AND INTERFACES
Valve Pack No.1	10x Bi-directional Valves with proportional flow control, each with max flow 8 l/min. Pressure on VP controlled by VP No.3.
Valve Pack No.2	10x Bi-directional Valves with proportional flow control, each with max flow 8 I/min. Pressure on VP controlled by VP No.3.
Valve Pack No.3	<ul> <li>2x Bi-directional Valves with proportional flow and pressure control, each with max flow 32 l/min.</li> <li>2x Directional valves with proportional flow and pressure control, each with flow meter and max flow 150 l/min.</li> </ul>
Manifolds	Pressure and return manifolds mounted in front of the ROV.  1 x Pilot operated high flow valve with max flow 300 l/min on AUX system  1 x Pilot operated high flow valve with max flow 300 l/min on main system
Aux System Capacity	260 bar, 300 I/min
TELEMETRY/SE	INSOR CAPACITY AND INTERFACES
Telemetry Link	By default the control pod and telemetry system are prepared for survey operations. Up to 6 fibre optic cables are available for communication. Total capacity in a standard system is 8 composite video channels, 36 serial communication channels and expandable to include 4 HD video channels (all in a single optical fibre). Options are Ethernet, gigabit layer 1 (4 ports) with ethernet switch (4 ports), and Multibeam PECL.
Power Distribution	All power distributed to external users, such as lights, cameras and sensors can be switched on/off from the topside computer and are equiped with individual fuses. When a sensor is switched off, it's corresponding subsea connector is galvanic isolated. Total available power 20A @ 115VAC.  Available supplies: 115VAC, 24VDC, 48VDC, others on request.
Tool Interface	Max power consumption available is 20A @ 115VAC. Connector type: Seacon 5506-2008
Gyro Interface	Connector type: Seacon MinM-26#20, other on request
Sensor Interface	10 connectors are prewired for user/survey equipment. In addition 9 extra connectors can be installed.  Survey Sensors 1 to 9  Connector type: Seacon Min-K-10 - wired for 24/48VDC. Built in CP interface  Survey Sensor 10

CAMERA AND LIGHTS		
Camera Interface	Up to 9 composite video camera inputs. Connector type: Seacon 5506-1508 or MinL-coax One camera interface is combined manipulator communication and camera connector. HD is optional. F/Z lines are bipolar/VISCA/IP	
Pan/Tilt	Hydraulic and/or electrical	
Light Interface	Capacity for ten dimmable lights, maximum load of 30A. Each output secured by 6A breakers. Connector type: Seacon 5506-1503	
PERFORMANCE		
Bollard Pull FWD/AFT	900	
Bollard Pull LATERAL	850	
Bollard Pull Vertical UP	800	
Bollard Pull Vertical DOWN	900	
Speed FWD	> 1,7 m/s	
Speed LATERAL	> 0,9 m/s	

## **PILOT INTERFACE**

- Two identical pilot chairs, where all necessary controls for operating the ROV, TMS and PDU are integrated in the armrests.
- · Multiview Controllers
- Monitors
- Clearcom communication system, microphone and channel selectors integrated in pilot chair.

PDU	
Description	Two separate cabinets. One containing breakers, contactors, overload relays and signal transformers. The other serving as a termination and isolation point for all high voltage connections.
Input	3 phase 400-420-440VAC, 60 Hz (690VAC optional)
Output	ROV HPU 230 KVA, 4200-4350-4500VAC     ROV Instrument 10 KVA, 3000-3150-3300VAC     TMS HPU 23 KVA, 3000-3150-3300VAC     TMS Instrument 10 KVA, 3000-3150-3300VAC
CONTAINEDS (ODTION)	

CONTAINERS (OPTION)		
ROV Control Container	20' Container manufactured in accordance with DNV 2.7-1     Offshore Containers.     Dimensions: 6058 x 2438 x 3000mm (LxWxH)     Air conditioned     Option: Zone 2 certification	
ROV Workshop / PDU Container	20' Container manufactured in accordance with DNV 2.7-1     Offshore Containers.     Dimensions: 6058 x 2438 x 3000mm (LxWxH)     Air conditioned     Contain workshop, PDU and transformers.     Option: Zone 2 certification	

## TMS (OPTION)

Various options available. Contact Kystdesign for further information.





Connector type: Seacon Min-K-8 - wired for 115VAC.

